

BRUHAT BANGALORE MAHANAGARA PALIKE**DASARAHALLI ZONE**

Office of the Executive Engineer Dasarahalli Division
SCHDULE-B

**Name of Work:-Improvements to Drain at 2nd main 1st 'A' main& 3rd main road at
Difence colony in ward 14, Bagalagunte.**

SI	Description of Work	Unit	Qty	Sanctioned Rates		Amount
				In figures (Rs)	In Words (Rs)	
1	2	3	4	5	6	7
1	Earthwork excavation by manual means in hard soil involving an average horizontal throw upto 2 meters and an average lift upto 0.5 m, excavated surface leveled and sides neatly dressed, the disposed earth to be leveled neatly after breaking of clods complete as per specifications	Cum	78.60	90.72	Rupees Ninty & Seventy two Paise Only	7131.00
2	Removing B.S.Slab of drain and stacking etc., complete	Sqm	282.96	50.11	Rupees Fifty & Eleven Paise only	14180.00
3	Providing and laying in position plain cement concrete of mix M7.5 with OPC cement @180 kgs, with 40mm and down size graded granite metal coarse aggregates @0.85cum and fine aggregates @0.57cum machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	82.53	4211.38	Rupees Four thousand two hundred eleven and thirty eight Paise only	347565.00
4	Providing and laying in position plain cement concrete of mix M15 with OPC cement @240 kgs, with 20mm and down size graded granite metal coarse aggregates @0.878cum and fine aggregates @0.459cum, machine mixed, concrete laid in layers not exceeding 15 cms. thick, well compacted, in foundation and plinth, including cost of all materials, labour, HOM of machinery, curing complete as per specifications.	Cum	38.65	4690.50	Rupees Four Thousand six hundred ninty & fifty Paise Only	181264.00
5	Refixing stone slabs of drains and pointing in CM 1:3 etc complete	Sqm	282.96	70.04	Rueeps seventy & four paise only	19818.00
6	Providing Granite slabs selected quality roughly dressed and fixed in cement mortar (1:6) including fixing curing etc.,	Sqm	188.64	343.44	Rupees Three hundred forty three & forty four Paise only	64787.00
7	Providing and constructing precast concrete solid blocks with compressive strength not les than 35 Kg/sqm with cement mortar 1:4 masonry (quoin, Jamb, closer blocks) with solid concrete blocks of size 40x20x20 cms conforming to I.S: 2185/1965 in superstructure including cost of materials, labour charges, scaffolding, curing complete as per specifications.	Sqm	419.20	924.48	Rupees Nine hundred twenty four & Forty eight Paise Only	387542.00

Signature of the contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer.

8	Supplying and fixing precast reinforced concee slab 10cm thick including cost of reinforcement as per design and drawing material cost, transportation, hire charges of machinery, machine cutting the vertical face to get plain even surface stc., complete with all leads and lift conveyance charges, labour charges inclusive of cost of all materials.	Sqm	471.60	1600.00	Rupees One thousand Six hundred Only	754560.00
9	Disposal of debris to the final place of disposal with all lead and lift and as direction by the engineer in charge of the work, lead 4 Km a) Basic rate for haulage of materials as per item No. 17.4/KSRRB : M100-4.1 Rs. 2.00 Tonne/Km b) Average earth of work 1.28 Tonne/Km for Rs. 2.00/Km c) Add loading and unloading	Cum	78.60	78.24	Rupees Seventy eight & Twenty four Paise only	6149.00
					Total	1782996.00
					KRIDL Charges	215000.00
					misc	2004.00
					Grand Total	2000000.00

Signature of the Contractor

EXECUTIVE ENGINEER-4
KRIDL, BBMP, DIVISION,
BANGALORE-560 010

Executive Engineer